

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 4 W. . .

Crawford

COUNTY

DESCRIPTION OF CORNER 1/4 corner at center of Section 8

DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe

WITNESSES TO CORNER

10" B. Oak	-	N25E	-	19.9 feet
7" B. Oak	-	S46E	-	69.3 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a subdivision of Section 8. Set corner at intersection of true 1/4 lines. See map and minutes of survey of Section 8 subdivision. Falls 5.1' north and 12.75' east of iron stake previously established for center post- but obviously set from incomplete survey data.

Corner was placed and witnessed September 21, 1960.

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 9/27/60