

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T.  $\frac{26}{26}$  NR.  $\frac{4W}{5W}$

--- Crawford - Kalkaska --- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 7,18,12,13

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

5" Cedar - N89W - 16 $\frac{1}{2}$  links

4" Cedar - S13W - 88 links

6" Cedar - N24W - 32 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by single proportionate measurement between corners 1 mile north and 2 $\frac{1}{2}$  miles south by Forestry Division survey crew while making a partial resurvey of this township. No positive evidence of original Tamarack BFs.

Corner was placed and witnessed September 13, 1957.

SURVEYORS SEAL

SIGNED

*Billy D. Buckles*  
REGISTERED LAND SURVEYOR

DATE 10/30/57