

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 4 W. . . .

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16, 17, 20, 21 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

8" B. Oak - S68E - 25 links -----

6" W. Oak - S50W - 45 1/2 links -----

7" B. Oak - N45W - 54 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Probable original corner, set from probable line tree stumps 2.26 ch. west and 3.70 ch. east in place, and a Y. Pine bottom 3.64 ch. south. No evidence of original Oak and S. Pine BTs. Checks good for line and distance to 1/4 corner west.

Corner was placed and witnessed September 3, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 10/20/57
REGISTERED LAND SURVEYOR