

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W. . . .

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 7, 8, 17, 18. . . .

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap . . .

WITNESSES TO CORNER . . .

9" Cedar - S47E - 58 1/2 links . . .

7" Cedar - N27E - 23 1/2 links . . .

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by double proportionate measurement using
corners 1 mile west, Meander corner east, 1 mile south and 2 miles north, by
Forestry Division survey crew while making a partial resurvey of this township. A
possible position for government corner is S31E 39 links, but could not make positive
identification.

Corner was placed and witnessed September 5, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 10/30/57