

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W.

Crawford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 17, 18, 19, 20

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

12" J. Pine - N78E - 105 $\frac{1}{2}$ links

6" B. Oak - S31E - 150 links

6" B. Oak - N44W - 117 $\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by single proportionate measurement on E - W centerline of township, by Forestry Division survey crew while making a partial resurvey of this township. Checks for line and distance on north side Section 20, and swamps north and west. No evidence of original BT's. Corners 1/2 mile east and 1 mile west were used in the proportion.

Corner was placed and witnessed September 3, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 10/30/57
REGISTERED LAND SURVEYOR