

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W . .

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 18 & 19 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

7" Cedar - S19W - 10 links -----

10" Cedar - N57W - 26 1/2 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners, by Forestry Division survey crew while making a partial resurvey of this township. Could make no positive identification of government BT's. Check ok with stream east.

Corner was placed and witnessed September 4, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 10/30/57  
REGISTERED LAND SURVEYOR