

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W.

Crawford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 29, 30, 31, 32

DESCRIPTION OF CORNER MONUMENT Square stake

WITNESSES TO CORNER

7" R. Oak - N64E - 121 links

8" R. Oak - S36E - 227 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement using original 1/4 corner 1/2 mile east, established section corner 1 mile west, original section corner 1 mile north, and established section corner 1 mile south, by Forestry Division survey crew while making a survey of this township. Corner falls in large dirt stockpile so no iron was set at this time.

Corner was placed and witnessed August 5, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 10/30/57
REGISTERED LAND SURVEYOR