

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR. 4 W
26 4 W

Crawford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 5,6,31,32

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

10" J. Pine - N18W - 23 $\frac{1}{2}$ links

8" J. Pine - S71E - 47 $\frac{1}{2}$ links

7" J. Pine - S60W - 45 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by single proportionate measurement between probable original corner 1 mile east, and Houghton town corner 1 mile west, by Forestry Division survey crew while making a partial resurvey of this township.

Corner was placed and witnessed July 31, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 10/30/57
REGISTERED LAND SURVEYOR