

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W. . . .

Crawford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 5,6,7,8

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

9" Balsam - F3E - 67 $\frac{1}{2}$ links

8" Spruce - S88E - 24 links

5" Spruce - S36W - 22 $\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 1 mile east, 1 mile west, 1 mile north, 2 miles south, by Forestry Division survey crew while making a partial resurvey of this township.

Corner was placed and witnessed September 9, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 10/30/57
REGISTERED LAND SURVEYOR