

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W.

Crawford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 17 & 20

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

8" W. Oak - S24E - 4 links

9" E. Oak - S83W - 43 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a resurvey of this township. SE original BT in place with part of face, NW in place at correct distance but bears N84°W. 7" W. Pine stump for line tree 80 links west, possible Y. Pine line tree 4.79 east. Found evidence of original post when digging.

Corner was placed and witnessed August 30, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 10/30/57