

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W.

Crawford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 19 & 20

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

8" B. Oak - S36E - 26 1/2 links

9" W. Oak - S54W - 60 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners, by Forestry Division survey crew while making a partial resurvey of this township. Possible position for original corner based on 20" Y. Pine stump is S19W 17 links, but evidence is not conclusive.

Corner was placed and witnessed September 3, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 10/30/57  
REGISTERED LAND SURVEYOR