

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Crawford
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>26N</u> R <u>04W</u> | <u>K-8</u> |
| | T <u>26N</u> R <u>04W</u> | <u>K-9</u> |
| | T <u>26N</u> R <u>04W</u> | <u>L-9</u> |
| | T <u>26N</u> R <u>04W</u> | <u>M-9</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl R. Johnson, in a field survey on August 20, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found 1½" pipe in place from M. Schaaf Survey.

K-9 Found 1½" pipe in place from M. Schaaf Survey.

L-9 Corner re-established from witnesses in M. Schaaf Survey. Monument was lying approx. 25 feet east of proper location.

M-9 Found 1½" pipe in place from previous Department Survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 W½ corner section 24
 Found 1½" IP set in concrete
 R.Oak 14" N57E 26.9'
 R.Oak 10" S22E 33.8'
 R.Oak 10" S34W 43.3'
 R.Oak 10" N76W 17.7'
 R.Oak 8" S35W 30.2'

L-9 S½ corner section 24
 Found 1½" IP set in concrete
 Maple 10" S24W 23.0'
 R.Oak 12" N66W 33.2'
 R.Oak 8" N36W 9.8'
 R.Oak 14" S71E 29.7'
 R.Oak 12" S47W 17.3'

K-9 SW corner section 24
 Found 1½" IP set in concrete
 R.Oak 16" S71E 19.3'
 R.Oak 10" N22E 32.5'
 R.Oak 10" S82W 27.4'

M-9 SE corner section 24
 Found 1½" IP set in concrete
 W.Oak 30" N54W 55.6' Cherry 12" S77E 92.7'
 B.Oak 18" N14E 147.5' E of Trail Rd. East 118.0'
 B.Oak 12" S03E 144.4'

Signed by Carl R. Johnson
 Surveyor's Michigan License No. 30083

Date 9/17/90

