

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Crawford</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>04W</u>	<u>M-8</u>
	T <u>26N</u> R <u>04W</u>	<u>M-7</u>
	T <u>26N</u> R <u>04W</u>	<u>L-7</u>
	T <u>26N</u> R <u>04W</u>	<u>K-7</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl R. Johnson, in a field survey on August 20, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-8 Found 1½" pipe in place from a previous Department Survey.
 M-7 Found pipe in place from M. Schaaf Survey.
 L-7 Found pipe in place from a previous survey by Henning of section 13.
 K-7 Found sq. concrete in place from previous surveys of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>M-8 E½ corner sec. 24</u> Found 1½" IP set in concrete Oak 10" N55E 43.5' Oak 5" S68E 20.6' Aspen 12" N10W 27.8' Oak 16" S70W 39.9'	<u>L-7 N½ corner sec. 24</u> Found 1½" IP in concrete Spruce 8" N64W 4.4' Spruce 5" S13W 28.4' Spruce 5" S37E 45.1' Spruce 6" N22E 11.1'
<u>M-7 NE corner sec. 24</u> Found 1½" IP set in concrete Spruce 4" S34W 15.2' Spruce 6" S26E 21.3' Spruce 8" N34E 29.6' Spruce 6" N57W 30.6'	<u>K-7 NW corner sec. 24</u> Found 8" Sq. conc. mon. w/½" rod Oak 20" (clump of 4) S45W 27.9' Oak 8" S13E 24.2' Oak 6" S85E 35.0' cherry 12" NO3E 71.2'

Signed by Carl R. Johnson Date 8/17/90
 Surveyor's Michigan License No. 30083

