

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Crawford (County)	Located In	Corner Code #
1. Public Land Survey	T 26N R 4W	B1
	T 27N R 4W	B13
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on September 20, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- B 1 & B13 – GLO – Set ¼ post – J.H. Mullett – 1839
 - Pine 6" N75 ½°W 16 L.
 - Pine 6" N32°E 30 L.
- K.J. Ostling – 1956 – Set 4" brass cap on 1" pipe by single proportion between A13 (USGS Pipe) & E13 (Houghton Tile Mon.)
 - 7" J. Pine S52°W 19 L.
 - 9" J. Pine S55°E 70.5 L.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B1 & B13 – Standard ¼ corner common to Sec. 6, T26N, R4W & Sec. 31, T27N, R4W – Fd. 4" DOC (DNR) Brass cap on 1" iron pipe per DNR records. CL. of E-W Bit. Rd. is 87' N. DOC (DNR) Monument accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B1 & B13 – 4" DOC (DNR) Brass cap on 1" iron pipe.
 - Set Blue Carsonite Post 1' N.
 - S50°W 12.74' to set N & T in N side 13" J. Pine (KJO)
 - N4°E 3.89' to set N & T in W side 6" J. Pine scribed 'XBT'
 - S54°E 41.46' to set N & T in NE side 7" J. Pine scribed 'XBT'
 - S6°E 39.04' to set N & T in W side 3" J. Pine



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 4/11/2001