

RECORDED

MAR 29 2000

LIBER 4 PAGE 58

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 26N R 2W B-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

13 DEC 99 9:49 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on 16 SEPTEMBER, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11	●												
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1852 Norman F. Parker, R.L.S. #16939
- D.A. Pettibone, D.S. L.C.R.C Liber 2, Page 58, Liber 154, Page 51, Liber 154, Page 51, Liber 173, Page 274, Liber 192, Page 323
- Mon. - Post Mon: Found Concrete Monument set by G.D. Henning
- 12" Y. Pine S42°E 15 6" J. Pine South 14.6'
- 15" Y. Pine N80°E 53 6" J. Pine N24°W 12.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Concrete Monument of record in South edge of pine plantation.
Found 6" (now 12") Jack Pine South 14.6'
Found Jack Pine Stump N24°W 12.3'
Accepted Concrete Monument as the best available evidence of the position of the Original Corner, placed survey cap on concrete monument for identification purposes and left in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon: Left concrete monument in place with cap marked MEM 31600
- Wit:
- Set Spike in West face 12" Jack Pine South 15.09'
- Set Spike in North face 6" Jack Pine S51°E 5.01'
- Set Spike in North face 4" Jack Pine S78°W 16.12'
- Set Spike in Northeast face 4" Jack Pine N45°W 17.25'

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE NOV 30, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600



Date Dec 06, 1999