

MAR 29 2000

LIBER 4 PAGE 59

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CRAWFORD
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 26N R 2W B-12
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

13 DEC 99 9:49 A.M.

SANDRA HOWE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on 16 SEPTEMBER, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	(31)		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Norman F. Parker, R.L.S. #16939
LCRC (Liber 2, Page 172), (Liber 167, Page 475)
Mon: 1/2" bar at Center of Section 31
Wit: none provided

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron which falls 5.17' North and 35.48' West of the intersection of the 1/4 lines.
West 1/4 corner S89°54'04"W 2392.44'
East 1/4 corner N89°54'04"E 2609.14'
North 1/4 Corner N00°14'53"E 2629.65'
South 1/4 corner S00°14'53"W 2630.86'

This position was not established by original government survey. This position is accepted as a determination of the position of the corner and was verified by measurement to 1/4 corners as noted above. (Note: Bearings and distances recorded in a survey by N. Parker noted above support this position.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Place a Standard County Corner at the intersection of the 1/4 lines, corner falls 40' South of a East & West utility line.
Wit:

- Set spike 3" Jack Pine S26°W 4.34'
- Set spike 6" Jack Pine N24°W 16.13'
- Set spike 14" Norway Pine S88°W 33.85'
- Set spike 3" Jack Pine S53°E 20.47'
- 1/2" bar 5.17' North & 35.48' West



CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE NOV 30, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date 12-07-1999