

MAR 29 2000

SECTION

LIBER

4

PAGE

61

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

For corners in

CRAWFORD

(County)

Located In:

Corner Code #

13 DEC 99 9:49 A.M.

SANDRA MOORE
REGISTER OF DEEDS

1. Public Land Survey

T 26N R 2W

B-13

T 25N R 2W

B-1

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on 16 SEPTEMBER, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839	George D. Henning, R.L.S. #2240	Gerald McKelvey, P.S. #19001
James H. Mullet, D.S.	Unrecorded survey dated 1970	(Liber 143, Page 257) Feb 5, 1975
Mon. - Post	Mon: 1/2" iron in old post (Henning 1937)	Mon: 1/2" rod in Corner
12" Pine N52°W 54 lks	10" J. Pine N25 1/2°W 32.00'	10" J. Pine N65°W 51.15'
14" Pine N65°E 40 lks.	6" J. Pine S38°W 31.0'	6" J. Pine S37°E 67.2'
		U.S.F.S. Post East 32.95'

Gerald McKelvey, P.S. #19001	Norman F. Parker, P.S.#16939
LCRC (Liber 2, Page 6) 1975	LCRC (Liber 2, Page 82) 1976
Mon: 1/2" rod in Corner and Henning references	Mon: 1/2" bar set by G. Henning in 1937
10" J. Pine N25 1/2°W 32.30'	10" J. Pine N25 1/2°W 32.0'
10" J. Pine N40°W 41.11'	6" J. Pine S38°W 31.00'
6" J. Pine S38°W 80.90'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar of record; found 10" J. Pine N25 1/2°W 32.0; found 6" J. Pine S38°W 31.0; found spike NE side 14" J. Pine Stump N40°W 41.11'; found Accepted 1/2" bar as the best available evidence of the position of the Original Corner. Replaced 1/2" bar with Standard County Corner Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument
Wit: Spike in East side 3" J. Pine N28°W 55.84
Spike in East side Utility Pole N08°E 35.06
Spike in East side 10" J. Pine S25°E 41.40
Found blazed 12" J. Pine S06°W 20.45



CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE NOV 30, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date 12-07-1999