

LAND CORNER RECORDATION CERTIFICATE

COUNTY OF CRAWFORD

Filing Requirement of Act 74, Mich. P.A. 1970

FILED FOR RECORD THIS

5th DAY OF Jan 19 94 AT 11:15 am, IN LIBER 3 4c PAGE 125

Elizabeth Wicklund Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Table with columns: Crawford (County), Located In: (Town, Range, Section), Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

LIBER 3 PAGE 125

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column C and row 9.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - June 1852 D.A.Pettibone Mon. - Post WIT: 5" Y.Oak S29 1/2 E 1.28 chs. 2" W.Pine N57 E 16 lks. L.187, pg.321 Sept. 13, 1979 G.Henning Mon. - 3/4" Bar WIT: P.Pole S73 E 58.35' 10" J.Pine S33 W 46.10' 6" J.Pine N23 W 42.10' L.1, pg.131 LCRC Nov. 6, 1974 N.Parker Mon. - 5/8" Bar & Scribed Stake 22'± West of C N-S Road WIT: NBT 12" Oak N15 W 30.00' Nail in SW side P.Pole S80 E 58.07' NBD 6" J.Pine S35 W 29.35' Unknown date from F.J.Arleth Mon. & WIT: Same as above (L.187, pg.321) L.185, pg.57 Feb. 7, 1980 G.Henning Mon & WIT: Same as above (L.187, pg.321)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 30" Bar of record 24'± West of centerline of North - South road. Verified location by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon. - Set Std. Crawford County Monument WIT: Fd. 1/2" Bar in centerline N-S road S85 E 24.90' Fd. Nail S. side utility pole S71 E 58.37' Set Std. Nail & Tag NW side 12" J.Pine S37 W 46.22' Fd. Nail SW side 15" R.Oak N37 W 32.95' Fd. Blaze SE face 8" J.Pine N20 W 42.09'



Signed by Marvin E. Myers

Date December 27, 1993

Surveyor's Michigan License No. 31600

DATE December 20, 1993

PEER GROUP APPROVAL