

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>2W</u>	<u>C - 10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED FOR RECORD THIS
5th DAY OF Jan 1994 AT
11:15 am/pm, IN LIBER 3 4c
 PAGE 124
Elizabeth H. Wieland
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 124

I, Marvin E. Myers, in a field survey on December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - June 1852 D.A. Pettibone	L.192, pg.323 Nov. 13, 1980 N.Parker
Mon. - Post	Mon. - 3/4" Pipe
WIT: Pine N19°W 2.03 chs.	WIT: BT 8" Oak N40°W 24.60'
Pine S21°E 1.09 chs.	BT 8" J.Pine S30°W 44.20'
5" Pine S12°W 2.68 chs.	Power Pole S43°E 79.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" I.D. x 17" Pipe of record 24 feet± West of centerline of North - South Road verified location by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Set Std. Crawford County Monument
 WIT: Set Std. Nail & Tag NW side 10" J.Pine S34°W 44.25' (to old blaze 44.00')
 Set Std. Nail & Tag NE side 11" B.Oak N35°W 24.78' (to old blaze 24.35')
 Fd. nail NE side utility pole S39°E 79.48'
 Fd. nail S. side 11" Oak N86°E 80.92'
 Fd. blaze S. side 6" J.Pine N04°W 22.00'



Signed by Marvin E. Myers Date December 22, 1993
 Surveyor's Michigan License No. 31600

DATE December 20, 1993 PEER GROUP APPROVAL _____