

CRAWFORD COUNTY REMONUMENTATION STATE OF MICHIGAN
LAND CORNER RECORDATION CERTIFICATE COUNTY OF CRAWFORD
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>2W</u>	<u>C - 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED FOR RECORD THIS
5th DAY OF Jan, 1994 AT 4c
11:15 am /pm, IN LIBER 3
 PAGE 123.
Elizabeth S. Wickland
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 123

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - June 1852 D.A.Pettibone L.154, pg.51 May 3, 1976 N.Parker
- Mon. - Post Mon. - 1/2" Bar
- WIT: 6" Pine N10°W 10 lks. WIT: BT 6" J.Pine N39°W 23.20'
- 6" Pine S58°E 23 lks. BT 12" J.Pine S40°W 15.60'
- L.1, pg.131 LCRC Nov. 6, 1974 Telephone cable box N75°W 12.10'
- N. Parker C. Road is 24' East
- Mon. - 5/8" Bar L.2, pg.58 LCRC Aug. 3, 1976 N.Parker
- WIT: NBT 12" J.Pine S75°E 53.70' Mon. & WIT same as above
- NBT 10" J.Pine S40°W 15.40'
- NBT 6" J.Pine N45°W 23.00' L.181, pg.604 Oct. 1978 N.Parker
- Mon. & WIT same as above (L.154, pg.51)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" Bar of record alongside 3/4" x 31" Bar 27 feet± West of centerline North - South Road verified location by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon. - Set Std. Crawford County Monument
- WIT: Fd. SE corner of Utility riser at ground level N75°W 11.70'
- Fd. Nail E. side guy pole S25°W 33.19'
- Fd. Nail NE side 8" Oak S37°E 91.70'
- Fd. Nail N. side utility pole N76°E 62.60'
- Set Std. Nail & Tag S. side utility pole N79°W 13.57'



Signed by Marvin E. Myers

Date December 22, 1993

Surveyor's Michigan License No. 31600

DATE December 20, 1993

PEER GROUP APPROVAL