

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

For corners in

Crawford
 (County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|--------|
| 1. Public Land Survey | T | <u>26N</u> | R | <u>2W</u> | C - 12 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

FILED FOR RECORD THIS
5th DAY OF Jan, 1994 AT
11:15 am/pm, IN LIBER 3 4c
 PAGE 122.

Elizabeth S. Wieland
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 122

I, Marvin E. Myers, in a field survey on December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| GLO - June 1852 D.A.Pettibone
Mon. - Post | L.2, pg.58 LCRC Aug. 3, 1976 N.Parker
Mon. - 1/2" Bar |
| WIT: 8" Pine S31°40'E 5.52 chs.
8" Pine S80°30'W 4.33 chs. | WIT: Face of Power Pole N35°W 45.10'
Face of guy pole N65°E 58.50'
Cor. is 24' W. of C N-S road |
| 8-26-70 Henning
Mon. & WIT not given | L.167, pg.475 Jan. 11, 1978 N.Parker
Mon. & WIT same as above (L.2, pg.58 LCRC) |
| | L.2, pg.172 LCRC Jan. 11, 1978 N.Parker
Mon. & WIT same as above (L.2, pg.58 LCRC) |
| | L.181, pg.604 Oct. 3, 1978 N.Parker
Mon. & WIT same as above (L.2, pg.58 LCRC) |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 30" bar 25 feet± West of centerline of road verified position by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon. - Set Std. Crawford County Monument
 WIT: Fd. nail NW side 9" J.Pine S30°W 15.09'
 Fd. nail NE side 12" Oak S38°E 81.12'
 Fd. PK nail SE side guy pole N60°E 58.53'
 Set Nail & Tag SW side of utility pole N34°W 45.74'



Signed by Marvin E. Myers

Date December 22, 1993

Surveyor's Michigan License No. 31600

DATE December 20, 1993

PEER GROUP APPROVAL _____