

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

For corners in

FILED FOR RECORD THIS
5th DAY OF Jan, 1994 AT
11:15 am, IN LIBER 3 PAGE 121 4/c
Elizabeth H. Wieland
 Register of Deeds

<u>CRAWFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>2W</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 121

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO 1839 H. Brevoot Jr. Aug 1970 G. Henning
 J.H. Mullett Mon- 1/2" bar in Old Wood Post in Road
 Mon-Post Wit- 10" J. Pine N64°W 51.15
 Wit- 8" Pine N46°W 141ks 6" J. Pine S37°E 67.2
 6" Pine N33E 71ks Corner by Henning 1932 USFS
 Date unknown Co. Surveyor E. Richardson
 Mon- Unknown found original bearing tree
 Wit- 6" B. Oak N64W 1.00 chains
 18" Y. Pine Stump N22 1/2°E 1.17 chains

I,2 P 82 LCRC April 1976 N. Parker
 Mon- 1/2" bar and old pipe south & 4.2 West
 Wit- 10" J. Pine N64°W 51.15
 6" J. Pine S37°E 67.21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2"x21" bar in Cedar Post 1.5 West of Center line of N-S Road verified location by measurement to accessories of record and accepted as best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Mon- Set Standard Crawford County Monument.
 Wit- Found witness tag in S. side USFS post East 32.86
 Found nail in SE side 10" J. Pine N41°E 100.2
 Found nail in E. side 10" J. Pine N33°W 59.66
 SE corner "Stop" sign post S73°W 40.78
 Set standard nail and tag SW side 7" J. Pine S39°E 67.41 (to old blaze 67.21)
 Found 1 1/2" I.D. pipe S85°W 4.72
 U.S. Army Corps of Engineers BM # S-1 S58°E 45.86



Signed by Marvin E. Myers Date Dec 22, 1993
 Surveyor's Michigan License No. 31600