

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

For corners in
Crawford
 (County)

Located in: Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|-----|
| 1. Public Land Survey | T | <u>26N</u> | R | <u>2W</u> | D-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |

FILED FOR RECORD THIS
5th DAY OF Jan, 1994
 11:15 am IN LIBER 3 PAGE 4c
128
Edith M. Whelan
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 128

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--------------------------------|-----------------------------------|---------------------------------------|
| GLO-June 1852 D. Pettibone | L181 P. 81 Sept 1976 N. Parker | L355 P48 July 1987 M.E. Myers |
| Mon-Post | L. 188 P. 492 Sept 1976 N. Parker | Mon-3/4" Pipe |
| Wit-6" Pine N15°E 91ks | L. 2 P. 81 1977 N. Parker | Wit-8" J. Pine NW 114.8 |
| 6" Pine S6°E 3.15 chains | Mon-3/4" Pipe | End of Conc Gas Pump Island ENE 45.00 |
| | Wit- G M-72 South 64.5 | Center line M-72 South 64.5 |
| MSHD May 1960 L. Schmalzried | 12" J. Pine NW 114.8 | |
| Mon-3/8" steel pin in concrete | 8" J. Pine NE 66.8 | |
| Wit-10" J. Pine N40°W 94.05 | End of Concrete Island ENE 45.0 | |
| 8" J. Pine N38°E 102.28 | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 12" Cabin Spike over 1/2" bar in 18" below asphalt verified position by measurement to accessories of record and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- MON- Drove 1/2" bar down set in exact location standard Crawford County Monument.
 Wit-Centerline M-72 South 64.5
 14" J. Pine N W 114.8
 SW corner Concrete R?W marker post N32°E 71.9
 Nail in S. side 8" J. Pine N32°E 73.2
 Nail in S. side utility pole N70°W 86.5
 NW Corner of "STEPHAN BRIDGE ROAD" S76°W 39.80



Signed by Marvin E. Myers

Date DEC 21, 1993

Surveyor's Michigan License No. 31600

DATE Dec 6, 1993

PEER GROUP APPROVED