

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Crawford _____ Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T 26N R 2W M-2
 T _____ R _____

2. Property Controlling
 in Section S 1 T 26N R 2W 14
 S _____ T _____ R _____

3. Miscellaneous
 Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on June 15, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-2 G.L.O. Brevort Mullett 1839 Set quarter section post 14- Carl Johnson P.S. #30084 set this corner while doing a survey in the area.
 Wit: Pine 6 N22°W 15 links
 Pine 6 S45°W 40 links

June 17, 1954 The Michigan Department of Conservation survey crew set a 1" iron pipe with a 4" brass cap at a corner previously located by an unknown surveyor.
 Wit: 9" J. Pine N28°E 56 links
 9" J. Pine S20°W 50 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-2 Found a Michigan Department of Conservation monument. 14- Found 1/2" iron rod with P.S. cap #30084 as set by Carl Johnson.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Department of Conservation Monument 10" R. Pine S03°W 33.62' 4" J. Pine S74°W 20.12' 10" Oak N20°W 20.74' 7" Oak S62°E 38.04' Wooden Post North 1±	14- 1/2" iron rod with P.S. cap #30084 Wit: 5" Spruce N74°W 32.55' 5" Spruce S09°E 32.47' Utility Pole S46°E 23.99' 4" Balsam N09°E 11.81' Carsonite Post North 1±
---	---

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 7-7-04

