

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>1W</u>	<u>G-13</u>
	T <u>28N</u> R <u>1W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

[Signature]
 STATE OF MICHIGAN
 CRAWFORD COUNTY
 RECORDED
 19 DEC 97 2:36 P.M.
 SANDRA MOORE
 REGISTERED PROFESSIONAL SURVEYOR & FILE NUMBER

4. Lot No. _____, Recorded Plat **LIBER 3**
 5. Private Claims _____

PAGE 303

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on May 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. 1839
 James H. Mullet D.S.
 Mon: Post
 Wit: 22" Y. Pine N21°E 23 links
 10" Aspen N61W 82 links
 - Carlos LaGarica, Ausable State Forest
 Mon: Found Corner set 18" Monument
 Wit: Found SW & SE Stumps good and in place, NE stump good, NW hole, ran S01°42'W found line tree stump at 3.13 chains; found swamp 4 chains East; Highway is 1.20 chains North.
 Set Pits N45°E 0.50 chains & S45°W 0.50 chains.
 - GLO - 1858 W. Warner, D.S.
 Mon - Post
 Wit: 20 Y. Pine S20°E 30 lks.
 18" Y. Pine S80 °W 50 lks.
 - July 3, 1953 Dept. of Conservation
 Mon - 1" Pipe with brass cap, previously perpetuated by Marcus Schaaaf
 Wit: Found three original "BT'S" in poor condition.
 9" J. Pine N7°W 30 lks.
 9" J. Pine S50°W 56 lks
 - 1933 F. N. Smith for G.F. Delamater
 Mon - unknown
 Wit: 20" Y. Pine S44°E 94
 - L. 417, P. 606 F. King, P.S. Aug 13, 1996
 Mon - Found 1/2" Iron in centerline of E-W Road and on line with fence N-S
 Wit: 12" J. Pine N45°E 58.22
 6" J. Pine S30°E 38.58
 6" J. Pine S30°W 40.22
 15" J. Pine N40°W 66.20
 - Oct 6, 1989 Don Marlatt, P.S.
 Mon - Reset from DNR Witness
 Wit: Found 9" J. Pine N07°W 30 lks
 Found 9" J. Pine S50°W 56 lks.
 10" J. Pine S56°W 16.81 feet
 10" J. Pine N65°W 26.96 feet

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Jan 9, 1997
Marvin E. Myers MEM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar over top of 60d spike with flagging in centerline of E-W Road on line with fence N-S; found all accessories recorded in L. 417, P. 606. **This position was not accepted.**
 Found 1/2" iron; found three GLO BT's did not find the 10" Aspen; found Pits N45°E 0.50 chains & S45°W 0.50 chains; found 9" J. Pine N7°W 30 lks; found 9" J. Pine S50°W 56 lks; found 20" Y. Pine (stump)S44°E 94; found 10" J. Pine S56°W 16.81 feet and 10" J. Pine N65°W 26.96 feet. Replace in exact location with a Standard Crawford County Monument.
 Accepted this position as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument.
 Wit: Found 9" J. Pine N07°W 30 lks
 Found 9" J. Pine S50°W 56 lks.
 10" J. Pine S56°W 16.81 feet
 10" J. Pine N65°W 26.96 feet
 Set Carsonite Post North 2'
 Found 1/2" bar N63°02'18"W 192.55 in centerline of road on N-S fence line.

Signed by Marvin E. Myers Date Dec 15, 1997
 Surveyor's Michigan License No. 31600

