

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>27</u> N. R. <u>1</u> W.		E-4; E-5
2. PROPERTY CONTROLLING IN SECTION <u>9</u> T. <u>27</u> N. R. <u>1</u> W.		158.8' S. of E-3; 180.9' E. of E-3
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Crawford

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on March 29, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

180.9' E. of E-3  
DNR monument & red-top post  
19" W. Pine N33°E 64.6  
7" R. Pine N85°E 83.6


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-4 Found Schaaf monument, faced by G.F.D. witness, which appears to have been used in DeLaMater survey.
- E-5 Found 4"x4" square cedar post as established in previous survey by G. F. DeLaMater.
- 158.8' S. of E-3 Found Schaaf monument and northwest O.B.T. showing lower face.
- 180.9' E. of E-3 Found Schaaf pipe/concrete base at corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4	E-5	158.8' S. of E-3
DNR monument	5' of 1" pipe (north edge of pond)	DNR monument & red-top post
10" J. Pine S76°E 87.6	9" Spruce N42°W 56.2	7" R. Pine N69°W 38.1
5" J. Pine S19°W 58.6	12" Balsam N17°W 68.0	14" R. Pine N52°E 41.5
*7" J. Pine stump S42°E 19.6		24" W. Pine stump (O.B.T.) N72°W 11.3
*G.F.D. witness, 1939		

SIGNED BY Kenneth J. Ostling DATE 6-17-77  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CRAWFORD COUNTY