

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 27 N. ● R. 1 W. ●	F-3; F-4; G-3; G-4
2. PROPERTY CONTROLLING IN SECTION _____	T. 27 N. ● R. 1 W. ●	8
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. ● S. R. _____ E. ● W. ●	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Crawford

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 13, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**


**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- F-3 Found Houghton tile at corner.
- F-4 Set at calculated intersection of ¼ lines.
- G-3 Found Houghton tile at corner.
- G-4 Set corner by proportionate measurement between section corners, which appears to be position used by G.F.D. to subdivide section.
- 8 Set by standard survey procedure for subdivision of sections.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F-3	F-4	G-3
½" rod in concrete filled tile	2½' of 1" pipe	5/8" rod in concrete filled tile
12" Twn.R. Pine S39°W 62.5	9" Cedar N54°W 35.6	10" Twn.R. Pine N44°E 45.9
8" J. Pine N56°W 64.8	3" Spruce N14°E 14.0	4" J. Pine N73°W 47.9
		12" J. Pine Stmp. N54°E 38.4
		(old N.B.T.)
G-4	8	
DNR monument	1½" well point	
9" J. Pine S57°W 17.5	17" R. Pine S70°W 43.8	
3" R. Pine N36°E 93.6	9" Cedar S02°E 57.9	
1½" pipe in block of conc. S55°E 15.8		

SIGNED BY Kenneth J. Ostling DATE 6-7-74  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)