

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--:                          | LOCATED IN--:                                      | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>27</u> N. <u>●</u> , R. <u>1</u> W. <u>●</u> | B-7; C-6; D-5; D-7 |
| 2. PROPERTY CONTROLLING IN SECTION _____   | T. _____ N. _____ S., R. _____ E. _____ W. _____   | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ S., R. _____ E. _____ W. _____   | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |  |                    |
| 5. PRIVATE CLAIMS _____                    |  |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 27, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-7 Set corner at location previously restored by Schaaf in 1935 from U.S. evidence.
- C-6 Set by proportionate measurement between section corners. Schaaf monument gone.
- D-5 Restored Schaaf position for corner.
- D-7 Recovered Schaaf position as established in 1935 survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| B-7                   | C-6                     | D-5                      | D-7                   |
|-----------------------|-------------------------|--------------------------|-----------------------|
| Set DNR monument      | Set DNR monument        | Set 1½" Pipe/Conc. Block | Set DNR monument      |
| 7" R. Pine N40°W 13.2 | 10" R. Pine S30°E 114.5 | 9" R. Pine N18°W 24.9    | 8" R. Pine S28°E 29.1 |
| 14" W. Oak S41°W 38.6 | 6" R. Pine S30°W 95.3   | 8" R. Pine N64°E 28.4    | 12" W. Oak N20°E 16.7 |
| Cedar Post North 12'  | Cedar Post East 14'     | Cedar Post SW 18'        | Ced. Post South 11'   |

SIGNED BY *Kenneth J. Ostling* \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_