

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 27 N. R. 1 W. ●	G-6; H-5; I-5; I-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 19, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - ~~Description of original monument and accessories and/or subsequent restorations:~~

C. (continued)

I-6
Left conc./tile mon. in place
set cedar post
11" Oak N49°E 15.45
14" R. Oak S19°E 88.8


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-6 Found ½" iron bar in G road probably as established in G. D. Henning survey of this section. Schaaf pipe removed.
- H-5 Found pipe as established in Schaaf survey - probably in 1940's. Apparently used in subdivision of Section 15 by local surveys.
- I-5 Found 1¼" pipe as established in 1940's Schaaf survey of part of this township.
- I-6 Found Houghton tile at corner apparently used in local surveys for subdivision of Section 15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6	H-5	I-5
Left ½" Iron Bar in Place	Set DNR Mon. in Place of 1¼" pipe	Set DNR Mon. in Place of 1¼" pipe
6" J. Pine N68°W 73.0	5" Cedar S16°W 14.55	8" Oak S32°W 22.55
6" J. Pine S53°W 92.85	5" Cedar N21°W 8.48	4" Oak N26°W 22.9
		Set Cedar Post

SIGNED BY *Kenneth Ostling* DATE 11-15-78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY