

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	8 T. 27 N. R. 1 W.	D-3
2. PROPERTY CONTROLLING IN SECTION	8 T. 27 N. R. 1 W.	1; 4; 5
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl R. Johnson, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 10, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

See Continued

A. Description of original and subsequent locations:

- | | |
|-----------------------------|-----------------------------|
| 4 | 5 |
| Set 5/8" rod w/cap and post | Set 5/8" rod w/cap and post |
| Red Pine 10" S41°E 9.1' | Cedar 22" S63°W 29.2' |
| Red Pine 8" S59°W 10.7' | Red Pine 8" S13°W 32.5' |
| Red Pine 8" N52°E 10.4' | Northerly edge of stream |


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1 Set corner mid-way and on line between found section corner to West and 1/4 corner to East.
- D-3 Found corner in place as established by E.S. Houghton 1923.
- 4 Set by standard survey procedure for subdivision of sections.
- 5 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-----------------------------|--|
| 1 | D-3 |
| Set 5/8" rod w/cap and post | Found 4" conc./tile (Houghton Mon.) set post |
| Jack Pine 4" S28°E 17.9' | Red Oak 4" N40°E 4.4' |
| Red Pine 8" S44°W 40.4' | Red Oak 10" S23°W 15.0' |
| | Red Oak 5" S28°E 16.2' |

SIGNED BY *Carl R. Johnson* DATE 4/3/86
 SURVEYOR'S MICHIGAN REGISTRATION NO. 30083



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ Crawford County

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET