

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

For corners in

Crawford
(County)

Located In: Corner Code //

- | | | | |
|------------------------------------|---|---------|------|
| 1. Public Land Survey | T | 27NR 1W | D-13 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T R | |
| | S | T R | |
| 3. Miscellaneous Property in Sec. | S | T R | |
| | S | T R | |

FILED FOR RECORD THIS
6th DAY OF June, 1990 AT
9:30 (am) pm, IN LIBER 2
PAGE 338.

Elizabeth S. Wisland
Register of Deeds

Register of Deeds Stamp & File Number

1. Lot No. Recorded Plat
2. Private Claims

Norman C. Caldwell in a field survey on March 19 90

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

JOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- (D-13) Post set by Mullett in 1839.
Pine 8" N50°E .28 (18.48')
Pine 8" N50°W .08 (5.28')

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (D-13) 2" pipe in conc. block placed by Schaaf, 1934, from SE orig. BT.
Mon. destroyed by persons unknown.
A 5/8" x 24" bar placed by proportional distance by Gerschbacher, LS 18990.
N74°E 54.20' 10" Oak
N67°W 34.95' 8" Twin Oak
S15°W 35.34' 8" R. Pine
rec. in L 2, pg 319

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (D-13) Standard 1/4 cor. Sec. 32, T27N-R1W
Fnd. 5/8" bar w/2" alum. cap in 8" sq. conc. base in CL E-W Rd. Accepted as a careful & faithful reestablishment of the position of the original corner.
North 10' Carsonite Wit. Post N70°W 35.0' 6" R. Oak (R)
N65°E 54.2' 7" R. Oak (R)
S63°E 66.7' 12" R. Oak
S13°W 35.4' 6" R. Pine (R)
S20°W 27.6' 8" J. Pine

igned by *Norman C. Caldwell*
urveyor's Michigan License No. 12018

Date April 26, 1990

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

