

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

For corners in

Crawford  
(County)

Located In:

Corner Code //

- 1. Public Land Survey T27N R 1W E-7  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

- 4. Lot No. Recorded Plat
- 5. Private Claims

FILED FOR RECORD THIS  
6<sup>th</sup> DAY OF June, 1990 AT  
9:30 am/pm, IN LIBER 2  
PAGE 339.  
*Elizabeth Wiland*  
Register of Deeds

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, a field surveyor on March, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (E-7) Post set by Pettibone, July 19, 1852.  
Y. Pine 14" N23°W .12 (7.92')
- Y. Pine 14" S26°E .08 (5.28')

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (E-7) Pipe & conc. block placed by LaGuire, 1934 from NW & SE orig. BTs.  
K.J. Ostling, LS 10068 found mon.  
S55°W 55.3' 7" R. Pine  
S26°E 41.2' 6" R. Pine  
rec. in L 2, pg 41

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (E-7) Sec. cor. 16,17,20&21, T27N-R1W  
Fnd. 1 1/2" iron pipe by LaGuire, 1934.  
And is accepted as a careful & faithful perpetuation of the position of the original corner.  
North 5' Carsonite Witness Post  
S26°E 41.5' 8" R. Pine (R)  
S52°W 55.4' 7" R. Pine (K)  
N76°W 88.2' 9" R. Pine  
N04°W 94.2' Maple

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

signed by

*Norman C. Caldwell*

Date

April 26, 1990

Surveyor's Michigan License No.

12018

