

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 7-1, Mich. P.A. 1970

STATE OF MICHIGAN  
COURT OF CLERKS

FILED FOR RECORD THIS  
6th DAY OF June 19 90 AT  
9:30 AM PM, IN LIBER 2  
PAGE 344.  
*Norman C. Caldwell*  
Register of Deeds

For corners in

	Located In:	Corner Code //
Crawford		
1. Public Land Survey	T27N R 1W	E-12 F-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

Register of Deeds Stamp & File Number

Norman C. Caldwell  
in a field survey on March 19 90  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. Description of original monument and accessories and/or subsequent restoration:

(E-12) Post set by Pettibone, July 25, 1852.  
Spruce Pine 7" N39°W .09 (5.94')  
Spruce Pine 10" S30°E .35 (23.10')

(F-7) Post set by Pettibone, July 19, 1852.  
Y. Pine 20" N20°E .80 (52.80')  
Spruce Pine 20" S17°W 1.74 (114.84')

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-12) LaGuire placed pipe & conc. block at point of stake & both orig. BTs. 1934.  
K.J. Ostling, LS 10068 fnd. mon. Dec. 28, 1973.  
N73°E 16.4' 10" Twin Oak  
N06°W 105.0' 19" R. Pine  
N79°W 28.8' 2" R. Pine  
rec. in L 1, pg 11

(F-7) LaGuire fnd. orig. post 1934 & placed pipe & conc. mon. both orig. BTs in place.  
Henning, LS 2240, fnd & used this mon. in 1955.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-12) 1/4 cor. 32&33, T27N-R1W  
Fnd. DNR pipe w/cap. And is accepted as a careful & faithful perpetuation of the position of the orig. corner.  
West 10' Carsonite Witness Post  
N05°W 105.8' 24" N. Pine (old BT) (R)  
N55°E 17.2' 6" N. Pine (new BT)  
N80°E 16.7' 8" Oak (old BT) (R)  
S80°W 52.4' 12" Oak (new BT)

(F-7) 1/4 cor. 16&21, T27N-R1W  
Fnd. 1 1/2" pipe by LaGuire. And is accepted as a careful & faithful perpet. of the posit. of the orig. corner  
North 1' Carson. Wit. Post  
S24°E 36.2' Maple  
S16°W 43.1' R. Pine  
S88°W 69.3' Maple  
N10°W 54.4' R. Pine

signed by

*Norman C. Caldwell*

Date

April 26, 1990

Surveyor's Michigan License No.

12018

