

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Crawford (County)
Located In: Corner Code //

1. Public Land Survey T27N R1W - H-7
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN
COUNTY OF CRAWFORD
FILED FOR RECORD THIS
6th DAY OF June 1990
9:30 AM IN LIBER 2
PAGE 353
Norman C. Caldwell
Registered Land Surveyor

Register of Deeds Stamp & File Number

Norman C. Caldwell field survey on March 19 90
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

(H-7) Y. Pine 24" diameter for quarter post, July 17, 1852.
Y. Pine 20" N34°W .71 (46.86')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-7) LaGuire, 1934, fnd. stump of orig. cor. tree & witness tree
Henning, LS 2240, fnd. stump & placed 1/2" bar & cap, Aug. 14, 1959.
K.J. Ostling, LS 10068, fnd. bar in stump, Sep. 19, 1978.
South 70.41' 20" R. Pine } DISTANCES REVERSED ON D.N.R. RECORD
S80°W 32.65' 10" R. Pine }
rec. in L 2, pg 193.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-7) 1/4 cor. 15&22, T27N-R1W
Fnd. record 1/2" bar w/2240 cap in remains of orig. gov. cor. tree (L 2, pg 193). And is accepted as a careful & faithful perpetuation of the position of the orig. corner.
North 1' Carsonite Witness Post
South 32.5' 10" R. Pine (R)
S80°W 70.1' 22" R. Pine (R)
S55°W 21.3' 6" R. Pine
S15°E 16.2' P. Pole

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

signed by
Surveyor's Michigan License No. 12018

Date April 28

