

LIBER 2 PAGE 357
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD
 FILED FOR RECORD THIS
6th DAY OF *June*, 19*90* AT
9:30 AM/PM, IN BOOK *2*
 PAGE *357*

corners in	Located In:	Corner Code //
Crawford <small>(County)</small>		
Public Land Survey	T 27N R 1W	I-7
	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
Miscellaneous	S T R	
Property in Sec.	S T R	

Register of Deeds Stamp & File Number

Lol No. _____ Recorded Plat _____
 Private Claims _____

Norman C. Caldwell in a field survey on **March**, 19**90**
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as recited below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- I-7) Post set by Pettibone, July 17, 1852.
 Y. Pine 20" S81°W .16 1/2 (10.89')
 Y. Pine 20" S3°W .13 1/2 (8.91')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-7) LaGuire, 1934, placed pipe & conc. block by proportion.
 K.J. Ostling, LS 10068, fnd. mon. & replaced w/DNR pipe & cap, Sep. 19, 1978.
 S26°W 29.35' 4" R. Pine
 N75°E 13.8' 5" Oak
 rec. in L 2, pg 193
 C.E. Ostling, LS 12026, fnd. LaGuire pipe
 N39°W 64.7' 8" Oak
 S24°W 51.4' 14" Oak
 rec. in L 1, pg 12

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (I-7) Sec. cor. 14, 15, 22 & 23, T27N-R1W
 Fnd. DNR pipe & cap, 2 wood posts, white stake. Accepted as the best available evidence of the position of the original corner.
 North 1' Carsonite Witness Post
 N39°W 64.1' 15" Oak (R)
 S24°W 51.2' 15" Oak (R)
 N80°E 14.1' 7" Oak (R)
 N50°W 33.9' 6" N. Pine

_____ signed by
 Surveyor's Michigan License No. 12018

Date April 26, 1990

