

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
6th DAY OF June 19 1990  
9:30 am, IN LIBER 2  
PAGE 368.

*Elizabeth W. Wisland*  
Register of Deeds

Register of Deeds Stamp & File Number

or corners in

—Crawford— Located In: Corner Code: #

Public Land Survey	T 27N	R 1W	K-7
	T	R	
	T	R	
	T	R	
Property Controlling	S	T	R
In Section	S	T	R
Miscellaneous	S	T	R
Property in Sec.	S	T	R

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

Norman C. Caldwell in a field survey on March 19 90

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

- (K-7) Post set by Pettibone, July 17, 1852.  
Y. Pine 20" S50°E .13 (8.58')  
Y. Pine 20" N73°E .47 (31.02')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (K-7) LaGuire, 1934, fnd. orig. post & both orig. BTs, placed pipe & conc. block mon.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (K-7) Sec. cor. 13, 14, 23 & 24, T27N-R1W

Fnd. 1 1/2" pipe in conc. block by LaGuire, near CL E-W road & 10' E. of CL road South. And is accepted as a careful & faithful perpetuation of the position of the orig. corner.  
North 20' Carsonite Witness Post  
N55°W 51.0' 2 1/2" angle iron 4' tall  
North 30.9' P. Pole  
N65°E 47.5' 12" Oak (old BT)  
S45°E 122.1' 8" N. Pine

signed by *Norman C. Caldwell* Date April 26, 1990  
Surveyor's Michigan License No. 12018

