

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
6th DAY OF June, 1990 AT
9:30 am, IN LIBER 2
PAGE 370.
Edith H. Wiland
Register of Deeds

or corners in
Crawford
(County)

Located In: _____ Corner Code: K-9

Public Land Survey T 27N R 1W _____ K-9
T _____ R _____
T _____ R _____
T _____ R _____

Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Norman C. Caldwell a field survey on March, 19 90,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

K-9) Post set by Pettibone, July 19, 1852.
Spruce Pine 12" N78°E 1.43' (94.38')
Spruce Pine 8" N29°W 1.90' (125.40')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9) Houghton placed a clay tile mon. (date unknown)
LaGuire accepted mon in 1934.
K.J. Ostling, LS 10068, fnd. mon. 8-28-72
S42°E 62.5' 5" R. Pine
S73°W 68.9' 8" J. Pine
S40°E 46.1' 12" J. Pine
N49°W 39.7' P. Pole
rec. in L 1, pg 15
C.E. Ostling, LS 12026, fnd. mon. Aug. 20, 1974.
S42°E 62.5' 5" R. Pine
S73°W 68.9' 8" J. Pine
S40°E 46.1' 12" J. Pine
rec. in L 1, pg 17

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9) Sec. cor. 23, 24, 25 & 26, T27N-R1W
Fnd. Houghton clay tile mon. buried 6" in CL N-S-E-W gravel
roads. Accepted as the best available evidence of the position
of the original corner.
S45°E 40' Carsonite Witness Post
N55°W 38.4' P. Pole
S30°W 64.3' Guy Pole
S30°E 46.5' 12" dead J. Pine (Old BT)
N60°E 69.0' 6" J. Pine

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Norman C. Caldwell Date April 26 1990
Surveyor's Michigan License No. 12018

