

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
6th DAY OF June 1990 AT
9:30 am, IN LIBER 2
PAGE 372
Edgar W. Wisland
Register of Deeds

or corners in
Crawford Located In: Corner Code K-11
(County)
Public Land Survey T27N R 1W
T R
T R
T R
Property Controlling S T R
in Section S T R
Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell field survey on March, 1990.
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

(K-11) Post set by Pettibone, July 19, 1852.
Spruce Pine 6" N40°W
Spruce Pine 5" West .21 (13.86')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-11) Houghton placed clay tile mon. (date unknown)
LaGuire, 1934, disregarded Houghton mon. & placed pipe & conc. block
5 links South
K.J. Ostling, LS 10068, utilized Houghton mon. for a Sec. retracement
dated Aug. 1972, project #72-29, plan #R-20-CC
Hughes, LS 20706, fnd. Houghton mon. Dec. 7, 1988
S38°W 17.90' 15" Oak
S39°E 14.08' 15" Oak
S25°W 39.11' 13" Oak
rec. in L 2, pg 305

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-11) Sec. cor. 25, 26, 35 & 36, T27N-R1W

Fnd. 5/8" iron in conc./clay mon. by Houghton. Accepted
as the best available evidence of the position of the orig.
corner.
North 1' Carsonite Witness Post S25°W 3.6' 1 1/2" LaGuire pipe
S38°W 18.0' 17" Oak (R)
S39°E 14.0' 15" Oak (R)
S30°W 43.2' P. Pole
N60°E 56.4' SW cor. garage

Witnessed by Norman C. Caldwell Date April 26, 1990
Surveyor's Michigan License No. 12018

