

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
6th DAY OF June 1990 AT
9:30 am, IN LIBER 2
PAGE 373
Richard W. Island
Register of Deeds

or corners in
Crawford Located In: Corner Code: K-12
(County)

Public Land Survey T 27N R 1W _____
T _____ R _____
T _____ R _____
T _____ R _____

Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Norman C. Caldwell in a field survey on March 1990

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

OTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- (K-12) Post set by Pettibone, July 19, 1852.
- Spruce Pine 12" S46°W .08 (5.28')
- Spruce Pine 12" S28°W .28 (18.48')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (K-12) King, LS 25852, fnd. 1 3/4" pipe in a survey dated July 6, 1984
- N81°E 25.78' 12" Oak
- S65°W 9.78' 8" Oak
- N32°W 17.65' 10" Oak
- rec. in L 226, pg 377

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (K-12) 1/4 cor. 35&36, T27N-R1W
- Fnd. 1 3/4" pipe in conc. block (LaGuire) per Fred King record. Accepted as a careful & faithful reestablishment of the position of the original corner.
- North 1' Carsonite Witness Post
- N81°E 25.8' 16" Oak (R)
- S65°W 9.7' 10" Oak (R)
- N32°W 25.7' 12" Oak (R)
- South 9.7' Fe. cor. post
- S35°W 69.5' P. Pole (angle)

signed by *Norman C. Caldwell*

Date April 2

Surveyor's Michigan License No. 12018

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

