

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD
FILED FOR RECORD THIS
16th DAY OF June, 1990
9:30 am, IN LIBER 2
PAGE 374
Elizabeth S. Wiland
Register of Deeds

or corners in
Crawford
(County)

Located In: Corner Code ##

Public Land Survey T 27N R 1W K-13
T _____ R _____
T _____ R _____
T _____ R _____

Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Norman C. Caldwell in a field survey on March, 1990
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

(K-13) Post set by Mullett in 1839.
Pine 10" N59°W .13 (8.58')
Maple 6" N59°E .10 (6.60')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-13) LaGuire, 1934, set a pipe & conc. block mon. from 2 orig. BTs.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-13) Stand. cor. 35&36, T27N-1W
Fnd. 1/2" bar, placed 12018 cap, @ S. shoulder of private E-W road, 2 1/2' N. of steel fe. post. And is accepted as a careful & faithful perpetuation of the position of the original corner.
South 0.5' Carsonite Witness Post
N35°E 29.4' 16" Poplar (old BT)
S05°W 31.6' 14" Poplar (old BT)
S35°W 19.8' 16" R. Pine
N50°W 47.0' 1/2" pipe & lath

Witnessed by Norman C. Caldwell Date April 6, 1990
Surveyor's Michigan License No. 12018

