

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in
Crawford (County) Located In: _____ Corner Code: L-7

Public Land Survey T 27N R 1W _____
T _____ R _____
T _____ R _____
T _____ R _____

Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____
Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
6th DAY OF June 1990
9:30 AM, IN LIBER 2
PAGE 375
Elizabeth Wislawa
Register of Deeds

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Norman C. Caldwell in a field survey on March, 1990,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- L-7) Post set by Pettibone, July 17, 1852.
Spruce Pine 9" N52°E .24 (15.84')
Spruce Pine 12" N47°W .10 (6.60')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-7) LaGuire, 1934, set a pipe & conc. block mon. by proportion.
K.J. Ostling, LS 10068, could not find mon., placed DNR pipe & cap
by proportion, June 19, 1979.
N47°E 8.9' 5" W. Oak
S45°E 16.81' 5" W. Oak
not recorded

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7) 1/4 cor. 13&24, T27N-R1W
Fnd. DNR pipe & cap @ N. edge E-W fireline. Accepted
as a careful & faithful reestablishment of the position
of the original corner.
North 10' Carsonite Witness Post
N80°W 54.3' 12" R. Pine
N10°E 12.4' 3" W. Pine (not blazed)
N20°E 6.8' red top post
N85°E 89.0' 4" R. Pine
S40°E 17.2' 7" W. Oak (R)

Witnessed by Norman C. Caldwell Date April 26, 1990
Surveyor's Michigan License No. 12018

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

