

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

corners in _____
Crawford Located In: _____ Corner Code: L-9
(County)

Public Land Survey T27N R1W _____ L-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
6th DAY OF June, 1990
9:30 am, in LIBER 2
 PAGE 376
Elizabeth D. Wisland
 Register of Deeds

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell in a field survey on March, 1990,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 present manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- L-9) Post set by Pettibone, July 21, 1852.
 Spruce Pine 11" N10°W .39 (25.74')
 Spruce Pine 4" S08°W .04 (2.64')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-9) LaGuire, 1934, set pipe & conc. block mon. by proportion.
 K.J. Ostling, LS 10068, fnd. mon. & replaced with DNR pipe & cap 9-5-72
 S38°W 23.3' 9" R. Pine
 S08°E 19.8' 10" R. Pine
 rec. in L 1, pg 14

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-9) 1/4 cor. 24&25, T27N-R1W
 Fnd. DNR pipe & cap, @ S. edge E-W fireline. Accepted as a careful
 and faithful reestablishment of the position of the original corner.
 South 5' Carsonite Witness Post
 S38°W 23.6' 14" N. Pine (R)
 S08°E 20.3' 15" N. Pine (R)
 S40°E 47.1' 16" N. Pine
 N30°E 46.7' 10" J. Pine

Witnessed by Norman C. Caldwell Date Apr 16, 1990
 Surveyor's Michigan License No. 12018

