

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in  
Crawford Located In: Corner Code #77

Public Land Survey T 27N R 1W M-8  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property In Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
9th DAY OF June, 1990 AT  
9:30 AM, IN LIBER 2  
PAGE 380  
E. J. Wick  
Register of Deeds

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell in a field survey on March, 1990.  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-8) Post set by Hodgson & Sibley, May 18, 1839.  
Pine 8" N43°W .12 (7.92')  
Pine 8" S32°W .26 (17.16')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8) No record of this position being found or perpetuated.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8) Stand. 1/4 cor. 24, T27N-R1W  
Placed #5 rebar w/12018 cap by single proportion between stand. cor. on Michigan Meridian.  
West 15' Carsonite Witness Post  
N54°W 55.4' 4" Maple  
N88°W 42.85' 8" Oak  
N56°E 41.0' 5" Maple  
S48°E 43.0' 6" Oak

Witnessed by Norman C. Caldwell Date \_\_\_\_\_  
Surveyor's Michigan License No. 12018

