

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

or corners in

Crawford
(County)

Located In:

Corner Code #1

Public Land Survey

T 27 N R 1W

M-12

T R

T R

T R

Property Controlling

S T R

in Section

S T R

Miscellaneous

S T R

Property in Sec.

S T R

FILED FOR RECORD THIS
27th DAY OF June 1990 AT
9:30 @/pm, IN LIBER 2
PAGE 384.

Richard A. Wisland
Register of Deeds

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell field survey on March, 1990,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
lines 1 and 2 above were in conformance with regulations and rules therofore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-12) Post set by Hodgson & Sibley, May 18, 1839.
Pine 6" S28°W .26 (17.16')
Pine 6" N38°W .45 (29.70')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12) LaGuire, 1934, placed pipe & conc. block mon. by proportion.
King, LS 25852 fnd. the mon. & placed a 1/2" bar & cap 0.76' West
on line between "closing cors." of Oscoda Co. July 6, 1984.
East 30.7' Fe. post
S52°E 41.25' P. Pole
S10°W 39.95' 8" J. Pine
N82°W 33.15' 10" Oak
rec. in L 226, pg 377

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12) Stand, 1/4 cor, 36, T27N-R1W

Fnd. 2" pipe in conc. block by LaGuire in N-S fireline.
Accepted as a careful & faithful reestablishment of the
position of the original corner.

West 10' Carsonite Witness Post
S50°E 40.7' P. Pole (F. King BT)
S10°W 40.3' 12" J. Pine (F. King BT)
S70°W 25.3' 14" Oak
N80°W 33.9' 12" Oak
West 17.4' Red top post

by Norman C. Caldwell Date April 25, 1990
Surveyor's Michigan License No. 12018

