

STATE OF MICHIGAN  
 COUNTY OF CRAWFORD  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Crawford  
 (County) Located In: Corner Code: #1

- |                                    |                   |       |
|------------------------------------|-------------------|-------|
| 1. Public Land Survey              | T27N R 1W         | M-13  |
|                                    | T ___ R ___       | _____ |
|                                    | T ___ R ___       | _____ |
|                                    | T ___ R ___       | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
|                                    | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___ | _____ |
|                                    | S ___ T ___ R ___ | _____ |

FILED FOR RECORD THIS  
 26th DAY OF June 1990 AT  
 9:30 am, IN LIBER 2  
 PAGE 385.  
*E. J. Wiland*  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Norman C. Caldwell in a field survey on March, 1990  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- (M-13) Post set by Mullett in 1839.  
 Pine 10" S29°W .63 (41.58')  
 Pine 12" N15°W .25 (16.50')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (M-13) Houghton placed a clay tile mon.  
 LaGuire, 1934, fnd. mon. & orig. BT SW.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (M-13) Stand. cor. 36, T27N-R1W  
 Fnd. 5/8" bar in conc. w/tile, placed LS 12018 cap, in W. wheel track N-S fireline trail. Accepted as a careful & faithful reestablishment of the position of the original corner.  
 West 5' Carsonite Witness Post  
 N60°E 42.7' anchor pole (old BT)  
 S80°E 61.5' 26" R. Pine (Old BT)  
 S45°E 36.7' 7" R. Pine  
 West 33.2' Fe. cor. post  
 N50°W 40.5' P. Pole (old BT)

Signed by Norman C. Caldwell Date April 26, 1990  
 Surveyor's Michigan License No. 12018

