

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

<b>FOR CORNERS OF--:</b>	<b>LOCATED IN--:</b>	<b>CORNER CODE NUMBER</b>
1. PUBLIC LAND SURVEY	T. 27 N. R. 2 W.	J-11, K-11; K-10; K-9
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 20, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accession and/or subsequent restoration:~~

C. (continued)

	K-9
	Set DNR Mon. in place of Pipe
	5" R. Pine S74°E 35.48
	6" W. Pine N23°E 37.36

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-11 Previously restored in 1951 at Schaaf location where USBT's were identified. Falls 57' north of E-W road centerline.
- K-11 Found 1 1/4" pipe at corner probably as established in 1940 survey by Marcus Schaaf. Falls in line roads N-E-W.
- K-10 Found 5/8" rod about 7' west of center N-S road, as established in previous survey. Falls midpoint on line between section corners.
- K-9 Found 1 1/4" pipe at corner, probably as established in Schaaf survey in 1940's. Used in other surveys in Section 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11	K-11	K-10
Left DNR mon. in place	Set DNR mon. in place of 1 1/4" pipe	Left 5/8" Rod in Place
5" J. Pine N74°W 45.55	12" J. Pine S20°W 27.25	8" R. Pine N75°E 76.75
*5" J. Pine N77°W 43.95	8" J. Pine S60°E 25.85	14" R. Pine S39°E 110.6
*6" Dead J. Pine N07°W 37.35		
*7" Dead J. Pine N03°W 50.75		
*Old NBT's		

SIGNED BY Kenneth J. Ostling  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 11-78

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CRAWFORD COUNTY