

Crawford ✓

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. <u>30</u> R. <u>3</u> <u>W.</u>	B-1 B-3 C-3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11-29 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1. Set corner by proportionate measure between section corners. No valid previous corner.
- B-3. Set corner by proportionate measure between section corners. No previous corner.
- C-3. Set corner at intersection of trail road N-S and E, which falls about 21.5' East of N-S power line, as do all other corners for several miles North and South. Disregarded 1-1/4" pipe by M.D.S.H.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1	B-3	C-3
Set DNR Mon.	Set DNR Mon.	Set DNR Monument
6" H. Maple S58E 86.7'	7" Maple clp S17E 30.8'	12" R. Pine N47E 58.5'
10" H. Maple N18E 92.3'	14" W. Oak S60E 83.8'	16" Tw Maple S52E 49.5'
		1 1/4" pipe & Bolt West 21.5'
		N-S Power Line West 21.5'


SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____