

CRAWFORD ✓

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. R. <u>3</u> E. W.	C-1 C-2
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	, T. <u>27</u> N. R. <u>3</u> E. W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. R. _____ E. W.	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 10-27-72 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-1 Found pipe & bolt set by MDSH at position of Sq. Cedar Post. All evidence indicates this to be the same position that Houghton's notes show
- C-2 Set corner by proportionate measurement between section corners.
- 2 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1	C-2	Code 2
Set D.N.R. Monument	Set D.N.R. Monument	Raset old conc. & Tile & Brass Cap State Mich. Mon.
6" W. Pine S82W 40.7'	9" R. Pine N80W 73.5'	3" R. Pine S87E 19.1'
6" W. Pine S40W 84.2'	Face of P.P. S20W 73.15'	2 1/2" Sq. Con Mon S83E 18.8'
2 1/2" Sq. Conc. Mon West 28.0'	4" W. Pine N73E 27.45'	4" W. Pine S10E 68.1'
	N-S Power Line West 21.5'	

SIGNED BY Kenneth J. Ostling DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
 APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)