

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27 N. R. 3 W.	E-7; F-7
2. PROPERTY CONTROLLING IN SECTION	21, T. 27 N. R. 3 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 30, 1978 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- E-7 Found pipe as established by Schaaf in 1934 and accepted by G. F. DeLaMater in 1947 survey. Claimed to be set from U.S. evidence.
- F-7 Found corner as established in 1934 Schaaf survey, purportedly from U.S. evidence. Used in previous subdivision of Section 21.
- 1 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7	F-7	1
Fd. 1 1/4" pipe-set DNR Mon. & cedar post	Fd. 1 1/2" pipe-set DNR mon. & cedar post	Set 5/8" Rod w/RLS Cap & ced.post
MSHD tag in 16" R. Pine N40°W 65.49	18" Cedar S55°E 18.50	15" W. Pine S43°W 33.55
MSHD tag in 18" R. Pine S40°E 44.66	18" Cedar N77°W 18.45	14" R. Pine N07°E 23.78
MSHD tag in 20" R. Pine N71°E 76.05		3/4" Pipe N18 1/2°W 33.93

SIGNED BY Kenneth J. Ostling
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 11-15-78



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY