

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	E 27 N R 3 W	I-3; I-1; I-5; J-3
2. PROPERTY CONTROLLING IN SECTION	N R W	
3. MISCELLANEOUS PROPERTY IN SECTION	N R W	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirement of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 24, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 24, 1979, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories said or subsequent restoration.

C. (continued)

	J-3	
	Set DNR Monument	
	6" Cedar	S73°E 17.8
	10" Cedar	N39°E 25.55

B. Description of corner evidence found and or method applied in restoring or re-establishing corner.

- 3 Set by single proportionate measurement between section corners 1 mile N and S.
- 4 Set by proportionate measurement between section corners; corner is in W side of trail road N and S.
- 5 Fd. 1" pipe at corner as established in State park survey, probably by Granger. Fits good for line and measurement north and south.
- 3 Set by proportionate measurement between section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-3	I-4	I-5
Set DNR Monument & Cedar Post	Set DNR Monument	Set DNR Monument
4" R. Pine S15°E 7.28	12" R. Pine N50°W 14.62	12" R. Pine S45°W 8.0
6" Maple N47°E 15.51	12" R. Pine S40°W 23.12	11" R. Pine N15°W 14.5
	Red-Top Post 5.0' W	

SIGNED BY: [Signature] DATE: _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES.

SIGNED BY: _____ DATE: _____

APPROVED AND SIGNED BY: _____ DATE: _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CRAWFORD COUNTY